

ORDINANCE NO. C-83-77

AN ORDINANCE TO AMEND SECTION 1103.02 (b) and (c)(1) and (3)
AND TO INCLUDE SUBPARAGRAPH (4) OF THE CODE OF ORDINANCES
ENTITLED "REFERENCE SPECIFICATIONS" FOR SITE IMPROVEMENTS

BE IT ORDAINED BY THE COUNCIL OF THE CITY OF GROVE CITY, STATE OF OHIO,
THAT

SECTION 1. Section 1103.02 (b) of the Code of Ordinances which reads:

(b) Table A

<u>Type of Work</u>	<u>Reference Specifications</u>	<u>Standard Construction Drawing</u>
Earthwork	Section 200 "EARTHWORK", ODTS	ODT
Roadway bases	Section 300 "BASES:", ODTS	CGC
Roadway pavement	Section 400 "FLEXIBLE PAVEMENT" AND Section 450 "RIGID PAVEMENT:", ODTS	CGC
Structures	Section 500 "STRUCTURES:", ODTS	ODT
Incidentals (see Note #1)	Section 600 "INCIDENTALS", ODTS	See Note #2
Sanitary Sewer system	Section 900 "SEWAGE WORK:", and Item 640 :MANHOLES, CATCH BASINS, AND INLETS", CCS	CGC and CCS
Waterline system	Section 800 "WATER SUPPLY and DISTRIBUTION", CCS	CC
Roadside and unpaved areas	Section 650 "'ROADSIDE:", ODTS	CGC and ODT

Note 1. All work on sanitary sewer systems shall be governed by the Type of Work heading of Sanitary Sewer System, rather than the Incidentals.

Note 2. All incidental details not covered by the Grove City Standard Drawings shall be constructed in accordance with the State of Ohio Department of Transportation Standards Construction Drawings.

IS HEREBY AMENDED TO READ:

(b) Table A

<u>Type of Work</u>	<u>Reference Specifications</u>	<u>Standard Construction Drawing</u>
Earthwork	Section "200 EARTHWORK", ODTS	
Roadway Bases	Section "300 BASES", ODTS	CGC
Roadway Pavement	Section "400 FLEXIBLE PAVEMENT", and Section "450 RIGID PAVEMENT", ODTS	CGC
Structures	Section "500 STRUCTURES", ODTS	ODT
Incidentals (see Note #1)	Section "600 INCIDENTALS", ODTS	ODT & CGC
Roadside and unpaved areas	Section "650 ROADSIDE", ODTS	ODT
Waterline System	Section "800 WATER SUPPLY & DISTRIBUTION", CCS	CC & CGC (see Note #2)
Sanitary Sewer System	Section "900 SEWERAGE WORK", CCS	CC & CGC (see Note #2)

Note 1. All work and material pertaining to sanitary sewer construction shall be governed by Section "900 SEWERAGE WORK" of the City of Columbus "Construction and Material Specifications" unless modified, herein, by the Grove City Standard Drawings or the approved construction plans and documents.

Note 2. The City of Grove City Standard Drawings will govern all work unless some other standard drawing or detail on the plans is specified. In the absence of any Grove City drawings or detail, the appropriate City of Columbus Standard Drawing will govern.

SECTION 2. Section 1103.02 (c) (1) which reads:

(c) The following are modifications to the reference specifications of Table A:

- (1) Sidewalk: 608.03(c) is changed by deleting the next to last sentence that pertains to construction joints around manholes etc., and the last sentence is changed to read: "Premolded expansion joint material 1/2-inch thick shall be installed between the walk and any fixed structure or object such as manholes, sign posts or utility poles." 608.03 (d) is changed to read "transverse slope of 3/8-inch per foot."

IS HEREBY AMENDED TO READ:

- (1) Sidewalks: 608.03(c) is changed by deleting the next to last sentence that pertains to construction joints around manholes etc., and the last sentence is changed to read: "Premolded expansion joint material 1/2-inch thick shall be installed to the depth and across the width of the walk or abutting surface at intervals of thirty feet (30') minimum and between the walk and any fixed structure or object such as manholes, sign posts or utility poles." 608.03(d) is changed to read "transverse slope of 3/8-inch per foot."

SECTION 3. Section 1103.02 (c)(3) which reads:

- (3) Sanitary sewer system: In addition to the materials permitted in 901.02, the following pipe materials shall be permitted-----

IS HEREBY AMENDED TO READ:

- (3) Sanitary Sewer System: The materials permitted shall be governed by those identified in the General Notes or detail sheets of the approved construction plans and/or the Contract Documents. CCS, Section 901.10 is deleted. See Section 1103.03 (d) of this code for test requirements.

SECTION 4. Subparagraph (4) is hereby enacted to Section 1103.02 (c) and shall read:

- (4) Storm Sewer System: The materials permitted shall be governed by those identified in the General Notes or detail sheets of the approved Construction Plans and/or Contract Documents.


SECTION 5. This ordinance shall take effect at the earliest opportunity allowed by law.


Submitted: 11/7/77

Passed: 11/21/77

Effective: 12/21/77


Robert E. Evans, President of Council


Michael T. Brandt, Mayor

Attest: 
June A. Cook, Clerk of Council

I Certify that this ordinance is correct as to form:


Ronald E. Plymale, Director of Law